County of Orange Dana Point Marinas Workshop No. 5 "Marina Planning"

Meeting No. 6 January 30, 2007





Dana Point Marinas

Project Considerations

- Age & Dock Condition
- Existing Boater Feedback
- Design Criteria and Codes
- Coastal Commission Recommendations
- Oversized Boats in Ex. Smaller Slips
- Waitlist
- Market Demand (Longer and Wider)
- Harbor Water Depth
- Economic & Financial Considerations





AGENDA Workshop No. 5

- Commercial Core Projects Update
- Questionnaire Responses Additional Public Input
- Cost & Revenue Comparisons
- Proposed Design Alternative (Layout 2)
- What's Next? (Feb 20 Workshop)
 - CEQA
 - Phasing Plans
- Questions & Answers





DANA POINT HARBOR MARINAS LAYOUT COMPARISON

4 slip categories

SIZE	EXISTING	% OF TOTAL	LAYOUT 1	% OF TOTAL	LAYOUT 2	% OF TOTAL	LAYOUT 3	% OF TOTAL	LAYOUT 1 W/ CHANNEL ENCR.	% OF TOTAL	LAYOUT 2 W/ CHANNEL ENCR.	% OF TOTAL	LAYOUT 3 W/ CHANNEL ENCR.	% OF TOTAL
30' & Under	1795	75%	927	49%	852	45%	998	54%	953	49%	901	45%	1007	54%
31' to 38'	273	11%	518	27%	656	34%	380	21%	542	28%	689	34%	385	21%
39' to 49'	236	10%	325	17%	298	16%	333	18%	340	17%	319	16%	336	18%
over 50'	105	4%	119	6%	100	5%	135	7%	119	6%	100	5%	135	7%
TOTAL	2409	100%	1889	100%	1906	100%	1846	100%	1954	100%	2009	100%	1863	100%
NET GAIN/LOSS			-520		-503		-563		-455		-400		-546	
AVG SIZE	29.85		34.04		34.16		33.98		34.03		34.12		33.96	

DANA POINT HARBOR MARINAS **LAYOUT COMPARISON**

9 slip categories

SIZE	EXISTING	% OF TOTAL	LAYOUT 1	% OF TOTAL	LAYOUT 2	% OF TOTAL	LAYOUT 3	% OF TOTAL	LAYOUT 1 W/ CHANNEL ENCR.	% OF TOTAL	LAYOUT 2 W/ CHANNEL ENCR.	% OF TOTAL	LAYOUT 3 W/ CHANNEL ENCR.	% OF TOTAL
20 - 24	250	10%	0	0%	1.00	0%	0	0%	0	0%	8	0%	.0	0%
25 - 29	1157	48%	501	27%	237	12%	889	48%	505	26%	249	12%	898	48%
30 - 34	391	16%	501	27%	674	35%	141	8%	523	27%	711	35%	141	8%
35 - 39	270	11%	443	23%	589	31%	348	19%	467	24%	622	31%	353	19%
40 - 44	129	5%	189	10%	186	10%	216	12%	204	10%	200	10%	219	12%
45 - 49	107	4%	136	7%	112	6%	117	6%	136	7%	119	6%	117	6%
50 - 54	57	2%	48	3%	40	2%	24	1%	48	2%	40	2%	24	1%
55 - 59	33	1%	28	1%	24	1%	56	3%	28	1%	24	1%	56	3%
60 & over	15	1%	43	2%	36	2%	55	3%	43	2%	36	2%	55	3%
TOTAL	2409	100%	1889	100%	1906	100%	1846	100%	1954	100%	2009	100%	1863	100%
NET GAIN/LOSS			-520		-503		-563		-455		-400		-546	
AVG SIZE	29.85		34.04		34.16		33.98		34.03		34.12	Ĭ	33.96	

Background

Twelve planning priorities govern future planning and implementation.

- Keep the Harbor's character and family atmosphere.
- Give a facelift/renovation to Harbor structures.
- Maintain a full-service Harbor.
- Do not commercialize the Island.
- Ensure the future of the Yacht Clubs.
- Improve water quality.
- Better utilize existing parking.
- Address overall mix of land uses.
- Provide more parking in commercial area.
- Keep existing parkland, beach and landscape buffers.
- Address balance of revenue and non-revenue generating land uses.
- Provide restrooms and showers near the docks.







Commercial Core Re-Development

- Planning Areas 1 & 2
 - Planning Area 1 Marine Services
 - Dry Stack Boat Storage Building
 - New Marine Retail Store
 - Surface Boat Storage
 - Parking
 - Planning Area 2 Day Use Commercial
 - 35,000 sf outdoor Festival Plaza
 - Construction of +/- 80,000 sf of Restaurant/Retail space oriented around the Festival Plaza (net increase of +/- 30,000 sf)
 - Demolition of +/- 50,000 sf of existing Restaurant/Retail space
 - Renovation of +/- 30,000 sf of Restaurant/Retail space
 - 2 level Parking Deck
 - +/- 400 additional parking spaces
 - New Boater Service Building






Before – From Dana Wharf Parking Lot



















General Information (Q1 & Q16)

Workshop 2 Data:

Total Questionnaires Returned:	115 ea.		
Power Boat Owners:	55	50%	
Sail Boat Owners:	56	50%	
Live Aboard Boaters:	4		
Dry Storage Boaters:	8		
Waiting List Boaters:	3		

Workshop 5 Data: (45 Additional Responses)

Total Questionnaires Returned:	160	ea.	Change
Power Boat Owners:	75	48%	- 2% -
Sail Boat Owners:	81	52%	+2%
Live Aboard Boaters:	6		
Dry Storage Boaters:	11		+3
Waiting List Boaters:	3		- 0 -



Existing Boat Mix of Respondents (Q2)

Workshop 2 Data:

	Total		
29 Ft. & Under	46	40%	
30 - 34 Ft.	23	20%	
35 – 39 Ft.	20	17%	
40 – 44 Ft.	16	14%	
45 – 49 Ft.	3	3%	
50 – 54 Ft.	6	5%	
55 – 60 Ft.	1	1%	

115 100%

Workshop 5 Data:

	To	Change	
29 Ft. & Under	69	43%	+3%
30 - 34 Ft.	32	20%	- 0 -
35 – 39 Ft.	27	17%	- 0 -
40 – 44 Ft.	18	11%	-3%
45 – 49 Ft.	4	3%	- 0 -
50 – 54 Ft.	9	5%	- 0 -
55 – 60 Ft.	1	1%	- 0 -

160 100%



Future Respondent Plans: Larger Boats (Q2 & Q6)

Workshop 2 Data:

<u> </u>							
	No. of						
Boat Size	Existing	Planned	%				
29 Ft. & Under	46	21	46%				
30 – 34 Ft.	23	12	50%				
34 – 39 Ft.	20	10	50%				
40 – 44 Ft.	16	6	38%				
45 – 49 Ft.	3	0	0				
50 – 54 Ft.	6	3	50%				
55 – 60+ Ft.	1	1	100%				

Average: 46%

Workshop 5 Data:

	No. of	Boats		
Boat Size	Existing	Planned	%	Change
29 Ft. & Under	69	27	39%	-7%
30 – 34 Ft.	32	16	50%	- 0 -
34 – 39 Ft.	27	10	37%	-13%
40 – 44 Ft.	18	8	44%	6%
45 – 49 Ft.	4	- 0 -	- 0 -	- 0 -
50 – 54 Ft.	9	4	44%	-6%
55 – 60+ Ft.	1	1	100%	- 0 -

Average: 41%



Dock Arrangement (Q13)

Workshop 2 Data:

Independent or Connected Walkway				
Independent Only:	73	66%		
Connected Walkway Only:	11	10%		
No Preference:	27	24%		

Workshop 5 Data:

Independent or Conn Walkway	Change		
Independent Only:	96	62%	-4%
Connected Walkway Only:	15	10%	- 0 -
No Preference:	44	28%	+4%





Dock Types (Q17)

Workshop 2 Data:

Dock Material Type Preference					
Concrete Only:	78	72%			
Wood Only:	4	4%			
Hybrid Only:	6	6%			
Multiple Preference:	21	18%			

Workshop 5 Data:

Dock Material Type	Change		
Concrete Only:	108	72%	- 0 -
Wood Only:	4	3%	-1%
Hybrid Only:	10	7%	+1%
Multiple Preference:	27	18%	- 0 -



Mooring Preferences/Main Channel Encroachment Opportunities (Q14, Q15 & Q20)

Workshop 2 Data:

Side-Tie Preference:	Yes	21	18%
Double-Wide Preference:	Yes	18	16%
Main Channel Encroachment:	Yes	63	55%

Workshop 5 Data:

Side-Tie Preference:	Yes	30	19%	+1%
Double-Wide Preference:	Yes	26	16%	- 0 -
Main Channel Encroachment:	Yes	96	60%	+5%





Change

Dry & Dinghy Storage (Q24 & Q25)

Workshop 2 Data:

Future Use of Dry Storage:	Yes	19	17%
Need More Dinghy Storage:	Yes	74	64%

Workshop 5 Data:

Future Use of Dry Storage:	Yes	25	16%	-1%
Need More Dinghy Storage:	Yes	101	63%	-1%



Change

Questionnaire Summary Results

- Same Basic Conclusions as Original Survey
 - Power vs. Sail
 - Boater Size Mix
 - Desire for Independent Docks
 - Desire for Concrete Docks
 - 16% of Boaters favoring Doublewides / 84% disfavoring
 - 41% of Respondents Planning to Purchase a Larger Boats
- Cost & Revenue Projections





Cost & Revenue Comparisons

(Without Channel Encroachment)

	36' Average 1,709 Slips (Larger Mix)	34' Average 1,889 Slips (Layout 1)	34' Average 1,906 Slips (Layout 2)
Construction Cost (1)	\$78,428,978	\$82,052,804	\$81,559,644
Cost Per Slip	\$45,892	\$43,437	\$42,791
Revenue / Year	\$14,932,112	\$14,911,843	\$15,337,405

(1) Mid Point of Construction: Mid 2011

(2) Ex. Marina Projected: \$15,547,947

(1) W/o ADA or DBAW compliance



Cost & Revenue Comparisons

(With Channel Encroachment)


	36' Average 1,805 Slips (Larger Mix)	34" Average 1,954 Slips (Layout 1)	34' Average 2,009 Slips (Layout 2)
Construction Cost (1)	\$81,392,951	\$85,104,117	\$84,755,099
Cost Per Slip	\$45,093	\$43,554	\$42,188
Revenue / Year	\$15,737,642	\$15,433,863	\$16,144,470


(1) Mid Point of Construction: Mid 2011

(2) Ex. Marina Projected: \$15,978,979

(1) W/o ADA or DBAW compliance







(WITH CHANNEL ENCROACHMENT)

OVER 50'

<-400>

29.85

71920

34.12

68544

Net Gain/Loss

Total LF

Average slip length

Dana Point Marinas

Project Phasing

- Awaiting ACOE Feedback
- 2 Options
 - 10 Phases: 212 to 310 boats per phase
 - 14 Phases: 135 to 235 boats per phase
- Upcoming Analysis
 - Detailed boat movement evaluation
 - o East & West Basin Mgmt Input
 - o Availability of Temporary Docks





Workshop No. 6 Agenda

- Further Refinements of Layout 2
- Further Development of Phasing Plans
- Dock Amenity Presentation
- Cost & Revenue Projection Refinements
- Date: February 20, 2007



